

INTERIOR DECORATION WORKS FOR UNITED INDIA INSURANCE CO. LTD.							
LARGE CORPORATE CELL D-24 & E-25, IInd FLOOR,HIMALYA HOUSE, 23 K.G. MARG,NEW DELHI - 110001.							
FOR LARGE CORPORATE CELL OFFICE AT I-29, IInd FLOOR,HIMALYA HOUSE, 23 K.G. MARG,NEW DELHI - 110001.							
ELECTRICALS							
S NO	ITEM / WORKS	UNITS	QTY	RATES IN WORDS	RATES IN FIGURES	Amount	TOTAL
2.00	<b>POINT WIRING</b>						
2.01	Supply and wiring of following switch controlled light point with 1.5 sq.mm PVC insulated multistrand EBCL Wire Suitable For 120 degree Temp. and Zero Halogen copper wire including PVC conduit recessed and/or on surface including flexible conduit chasing of wall, filling of chases etc. and/or fixing conduit on surface of wall/ceiling including fixing of saddles etc. including G.I. switch box, modular range of plate switches, modular cover plate, ceiling rose, surface or deep tee, 2.5 sq.mm circuit wiring, 1.0 sq.mm PVC insulated copper earth wire, etc. complete as required.						
	i Single/first LIGHT/FAN point.	No.	28.0				
	ii Looping points.	No.	5.00				
2.02	Wiring for 5A light plug point raw with 2x1.5 sq mm PVC insulated coper conductor wires in concealed surface PVC conduits/trunking including providing and fixing 5A grid plate mounted switch with moulded cover plate (with MK or eqv.) & 5A shuttered socket outlet,switch box complete as required	No.	20				
2.03	Wiring, P/F double 5A switch/socket (with MKor eqv.) with 2.5 sq.mm PVC cu wires	No.	15				
2.04	Providing and fixing 32A SPN socket outlet with wiring for ac metal clad MCB box with 32A DP including 2x6 sqm copper wire & 25m pvc pipe etc	No.	4.0				

S NO	ITEM / WORKS	UNITS	QTY	RATES IN WORDS	RATES IN FIGURES	Amount	TOTAL
2.05	Supply & wiring of power point (20 Amps.) with 2 x 4sq.mm PVC insulated multistrand EBCL Wire Suitable For 120 degree Temp. and Zero Halogen copper wire including PVC conduit recessed in ceiling/wall including chasing of wall, filling of chases with mortar etc. including galvanised MS outlet box, modular range 20Amp DP switch, flex outlet, cover plate, 4 sq.mm PVC insulated copper conductor earth wire etc. complete as required.	No.	2.0				
<b>3.00</b>	<b>TELEPHONE &amp; DATA SYSTEM.</b>						
	CONDUITING & WIRING FOR DATA & TELEPHONE						
3.01	Supply and fixing of RJ-11/45 telephone/data outlet on suitable M.S box with quard modular cover plate .	No.	16				
3.02	Supply and laying of Cat-6 data cable AT&T approved in recess PVC conduit complete as required. Per seat 3 cable	Mtr	900				
<b>4.00</b>	<b>SUPPLY AND INSTALLATION OF LIGHTING FIXTURES &amp; FANS</b>						
	Supply ,installation, testing and commissioning of the following fluorescent fixtures complete in all respect including chokes ,starters, tube holders, reflector assembly etc. including lamps Rate shall include all taxes and duties, transportation etc. complete.						
4.01	4x18 watts CFL Light Fixture as per Philips Cat No. TBS 669/414 D6HF2XEBT214	No.	8.00				
4.02	2X36 watts Flourescent Light Fixture as per Philips Cat No.TBS 518/236	No.	4.00				
4.03	WALL FAN	No.	6.00				
4.04	DOWN LIGHTER FBS075 2XPL-C/2P18W 1 240V	No.	10.00				
	<b>TOTAL COST OF THE ELECTRICAL WORKS</b>						