

**BOQ FOR UIIC SANGRUR**

S.NO	DESCRIPTION OF ITEMS	N	QTY	UNIT	RATE	AMOUNT
<b>INTERIOR WORKS</b>						
<b>1</b>	<b>WORK STATION</b>					
a)	<p>Providing and fixing of counter 2'-0" wide and 2'-6" high made up of 19mm BWP boards of approved makes as shown in drawings. There shall be provision for key board tray fixed with 2 nos ball bearing slide KA 270 (Hettich make). Low height storage space each comprising of 3 nos. of drawers 1'-3" wide of variable height for storage purposes fitted with bottom mounted drawer channels FR - 402 (Hettich make) having load carrying capacity upto 15 Kg. There shall be provision for keeping CPU underneath the table as/ detailed drawings. All exposed surfaces (such as table front, top, sides, key board tray, drawers) shall be finished with 1.00 mm laminate of approved make. All exposed edges of board shall be covered with pvc edge beading made out of 3/4" x 1 1/2".The inner surfaces shall be melamine polished. The work including fixing of the drawer auto locks, recess mounted handles and melamine polishing shall be completed in all respects to the entire satisfaction of Architect/BANK as per detailed Drawings.</p>	1	48	Rft		
<b>2</b>	<b>OFFICER TABLES</b>					
a)	<p>Providing and fixing of tables circular / stright upto 5'-0" longx2'-6"x 2'-6" high made up of 19mm BWP boards of approved makes. There shall be provision for key board All exposed surfaces (such as table front, top, sides, keyboard tray, drawers) shall be finished with 1.00 mm laminate Bavarian beech of approved make. There shall be provision for keeping CPU underneath the table as/ detailed drawings. There shall be providing and fixing of granite slab on top of table. All exposed edges of board shall be covered with teak wood beading made out of 3/4" x 1 1/2". The inner surfaces shall be melamine polished. The work including fixing of the drawer auto locks and melamine polishing shall be complete in all respects to the entire satisfaction of Architect as per detailed Drawings.</p>		7	Each		
<b>4</b>	<b>MANAGERS TABLE</b>					
a)	<p>Providing and fixing of Manager's table 6'-0"x2'-6"x 2'-6" high made up of 19mm BWP boards of approved makes. There shall be provision for key board tray fixed with 2 nos. ball bearing slide KA 270 (Hettich make). Low height storage spaces each comprising of 3 nos. drawers 1'-3" wide of variable height for storage purposes fitted with bottom mounted drawer channels FR - 402 (Hettich make) having load carrying capacity upto 15 Kg. All exposed surfaces (such as table front, top, sides, keyboard tray, drawers) shall be finished with 1.00 mm thk. laminate. There shall be provision for keeping CPU underneath the table as/ detailed drawings. 12mm glass shall be provided on top of table All exposed edges of board shall be covered with teak wood beading made out of 3/4" x 1 1/2". The inner surfaces shall be melamine polished. The work including fixing of the drawer locks and melamine polishing shall be complete in all respects to the entire satisfaction of Architect as per detailed Drawings.</p>	1	1	Each		
b)	<p>Providing and fixing of side runner 1'-6"wide made up of 19mm BWP boards of approved makes as shown in drawings. There shall be provision for storage cabinets high with sliding door shutters in front and one no. intermidate shelve. The sliding door shutter shall be 19 mm thk BWP board. All exposed surfaces</p>					

S.NO	DESCRIPTION OF ITEMS	N	QTY	UNIT	RATE	AMOUNT
	(such as table front, top, sides, working table top, drawers) shall be finished with 4.00 mm thk. Maple burl veneer with melamine polish of approved make. All exposed edges of board shall be covered with teak wood beading made out of 3/4" x 1 1/2".The inner surfaces shall be melamine polished. The work including fixing of the drawer locks, recess mounted handles and melamine polishing		3	R.ft		
5	<b>FULL HEIGHT GLAZED PARTITIONS</b> Providing and fixing aluminium partition with door (100 x 35mm)consist of 16 gauge powder coated/anodized aluminium section 75x75MM with powder coated/anodized aluminium beading , necessary rubber gaskets and 6mm thk. Clear glass with etching and with both side laminated MDF panel of GREEN MDF/NOVAPAN including all necessary hardwares , handles, mortice lock, floor spring, door stoper etc. complete in all respect.		520.00	Sq ft.		
6	<b>LOW HEIGHT PARTITIONS (partly glazed/partly paneled)</b> Providing and fixing of 4'-6"height partly glazed and partly paneled partitions made up of aluminium powder coating with laminated board		140	Sq ft.		
7	<b>VERTICAL BLINDS ON WINDOWS</b> Providing and fixing roller blinds on windows. Complete job including top rail, bolt on chains (tie) and weights etc. as per the shade approved by the Architect.		100	Sq ft.		
8	<b>STORAGE</b> Providing and fixing 2'-6" high storage racks made up of 19 mm BWP board on all sides, except the rear with 6 mm BWP ply. The width of each unit of cupboard shall be 1'-6" and spacing of 2'-6" with openable shutters and intermediate shelves shall be maximum @ 2'-0" c/c. All exposed surfaces shall be finished with 1.00 mm thick laminate bavarian beech of approved make and the internal surfaces with natural polish, handles, locks, teak wood leaping 6 mm thick and 19-38 mm wide, etc. as per the drawings		750	Sq ft.		
9	<b>ENTRY DOOR/ GLASS GLAZING</b> Providing and fixing aluminium door section styles and top rails 6"x 1.75" and bottom rail 6" x 1.75" and glazing with 12 mm thick tounged glass and glazing with itching and with necessary dorma/godrej fittings, complete in all respects . (inclusive of S.S door handle,floor machine, lock etc.)		160	Sq ft.		
10	<b>FALSE CEILING</b> a) Providing and fixing false ceiling curved/ stepped made gypsum board suspended with the help of necessary skeleton of channels as per India gysumboard with the help of ceiling angles and accessories complete and finaly finished with two or more coats of emulsion paint ( white / color) with necessary base prepration with putty, making cutouts for light fixtures, A.C grills, deffusers etc. complete in all respect to the entire satisfaction of architect.		2100.00	Sq ft.		
11	Providing and fixing PVC wall panelling of desired shade and design , complete in all respect.		200.00	Sq ft.		
12	Providing and fixing textured paint of desired shade and design , complete in all respect.		400.00	Sq ft.		

TOTAL

S.NO	DESCRIPTION OF ITEMS	N	QTY	UNIT	RATE	AMOUNT
------	----------------------	---	-----	------	------	--------