

**SCHEDULE OF QUANTITIES - INTERIORS WORKS FOR
UNITED INDIA INSURANCE COMPANY LTD, DO - NIZAMABAD**

S.No	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
1	INTERIOR WORKS				
	PARTITIONS				
a	FULL HEIGHT PARTITIONS - SOLID				
	Providing and fixing metal stud partitions with following specifications. (a) Supporting system comprising of Gypsteel/ Salwood (chemically treated) make 51mmx32mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical member should touch with horizontal ceiling/ channel at slab/beam bottom. The rate should also include necessary , strengthening with studs/tracks or channels at doors and other openings	Sft			
			230		
b	FULL HEIGHT PARTITIONS - PARTIALLY GLAZED				
	Same as Item no 1 but about 40% of the partition area shall be with 8mm Plain Glass of approved make with Etching & Acid texture design as suggested by the architect Steam beach beading size shall be 35mm x 12mm beech wood Molding duly polished. The size of the vision panel in all the doors shall be as directed at site.	Sft			
			410		
c	LOW HEIGHT PARTITIONS				
	Same as full height solid partitions but height shall not exceed 4'. All exposed edges shall be covered with 100 mmX12mm steam beech beading polished to melamine to look elegant. Wicket gate of matching quality shall be made wherever necessary using required SS hardware. Wicket gates shall be measured along with partition area only.	Sft	280		
	Total				
2	STORAGE UNITS(LHS & FHS)				
	Providing and fixing 450mm depth storage shelves using 18mm thick BWR grade plywood of IS 303 all over and intermediate shelves. Back shall be 12mm thick plywood. Internal surfaces shall be finished with a coat of putty and three coats of enamel painting. Exposed surfaces finished with 1mm thick laminate in multi colour and multi design as directed. Doors shall be using 18mm thick with double thickness at the edges) and fittings of SS make of company approved fittings. Front elevation area shall be measured for payment.	Sft	400		
3	MAIN ENTRANCE(4'-0"x7'-0')				

	Providing & fixing fully glazed 12mm toughened glass door at the main entrance and for consists with top and bottom patch fittings with dead lock.12 mm thk Saint Gobain clear float glass with sand blasting/etching (as per design) and finish handle(1'-0" long)of Neki/Hasseley maketo be fixed on both sides. The rate should include of United India Logo sticker and Etching works of approved make.The work to be completed in all respect as per design, direction and approval of the architect.	Sft	28		
	B FURNITURE WORKS				
	1 TABLE FOR D MGR				
	Managers Table overall size 6"x2'6" . 19mm thick plywood for Top and for pedestals . Top should be shown double thickness at the edges. 6mm for drawer bottom. 1.5 mm thick laminate for the top andall the exposed surfaces and 1mm thick laminate for all internal visible area of plywood . All the surfaces of the draws internally and externally should be covered with Imm thick laminate. All the draws and key board tray should slide on telescopic channels. All handles of Brush finished SS handles , Strap lock , Box hinges etc standard hardware. All the Exposed Edges of Plywood should be covered with 12mm thick plain Steam beech beading duly melamine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly melamine polished. 12mm thick plain glass with beveled edges on Table top should be provided. Cable manager provision to be provided in the table top even in glass. All as per the design andthe instructions of the design in charge.	EACH	1		
	2 OFFICER TABLE				
	Officer Table overall size 4'9"x2'6". 19mm thick plywood for Top and for pedestals . Top should be shown double thickness at the edges. 6mm for drawer bottom. 1.5 mm thick laminate for the top and all the exposed surfaces and 1mm thick laminate for all internal visible area of plywood . All the surfaces of the draws internally and externally should be covered with 1mm thick laminate.All the draws and key board tray should slide on telescopic chanel. All handles of Brush finished SS handles , Strap lock , Box hinges etc standard hardware. All the Exposed Edges of Plywood should be covered with 12mm thick plain Steam beech beading duly melamine polished. 24mm x 40mm thick Steam beech moulding for the Table top duly melamine polished. Cable manager provision to be provided in the table top even in glass. All as per the design and the instructions of the design in charge	EACH	7		

3	EMPLOYEE TABLES	No's	10		
	Officer Table overall size 3"-6"x2'6". 19mm thick plywood for Top and for pedestals . Top should be shown double thickness at the edges. Cable manager provision to be provided in the table.All as per the design and the instructions of the design in charge				
3	SLIDE UNITS				
	Side table of size 3'6"x2'6"x1'6"deep.19mm ply for all horizontal and verticals. One Key board tray made with 19mm plywood and 1mm lamination sliding on telescopic channels.. 9mm thick for the back side of the side table to be fixed. All exposed areas including back side should be covered with 1mm thick laminate and 1.5mm thick laminate for the Top. All Hardware matching to the Table. All as per the design and the instructions of the design in charge.	Sft	7		
	Divisional Manager Chair	No's	1		
	Chairs in Divisional Manager Cabin	No's	3		
	Officers Chair	No's	7		
	Visitor chairs for officers	No's	20		
	Executive Chairs	No's	11		
	Vistor Chairs in- line chairs 2 sets of 3 no's	No's	2		
	Furniture Total				

**SCHEDULE FOR THE ELECTRICAL WORKS FOR
UNITED INDIA INSURANCE COMPANY LTD, D.O. NIZAMABAD**

S.No	DESCRIPTION OF WORK	QTY	UNIT	RATE	AMOUNT
	Lighting/ Power/ UPS/AC/ LAN /Telephone Cabling Works				
	WIRING				
	Note: All Light/Ceiling Fan/Wall Mounting/Exhaust Fan/Bell Points Cost Including Circuit Wiring				
A1	Supply and wiring of Bell point with bell Push and Ding Dong Bell with Suitable Size 2mm thick PVC conduit with 3x1.5sqmm earth wire Copper multi strand flexible pvc insulated wires and 5A Switch cum sockets with Surface/Concealed Box with all required materials etc.				
	Supply.	1	Set		
	Fixing	1	Set		
A2	Supply and wiring of Wall Mounting Fan points from Near Switch Board with Suitable Size 2mm thick PVC Conduit with 3x1.5sqmm earth wire Copper multi strand flexible pvc insulated wires and 5A Switch cum sockets with Surface/Concealed Box with all required materials etc.				
	Supply.	5	Set		
	Fixing	5	Set		

A3	Supply and wiring of Ceiling Fan points with Electronic Step type type Regulators and 2mm Size PVC Conduits 3x1.5Sqmm earth wire Copper multi strand flexible pvc insulated wires and 5A Switch cum sockets with Surface/Concealed Box with all required materials etc.				
	Supply.	3	Set		
	Fixing	3	Set		
	Total				
D	MAIN PANEL AND SUB DBs				
D1	UPS OUTPUT DB: Supply & Installation, testing and Commissioning of the 12 way SPN Double door DB with 63/32A 2Pole MCB-1No as incomer, and Outgoings- 10/32A SP MCbs-10 Nos and all required materials etc.(MDS Legrand) For UPS Outgoing				
	Supply.	1	No's		
	Fixing	1	No's		
D2	UPS/AC DB:Supply and fixing of 4 Pole Enclosure with 4 Pole 63A MCB-1No For UPS Input				
	Supply.	1	No's		
	Fixing	1	No's		
D3	UPS:Supply and fixing of 4 Pole Enclosure with 4 Pole 63A Phase Selector switch with MCB-1No For UPS Input(3 Phase to Single Phase Converter)				
	Supply.	1	No's		
	Fixing	1	No's		
D4	UPS DB: Supply and fixing of 2 Pole Enclosure with 2 Pole 32A MCB-1 No for UPS Output				
	Supply.	1	No's		
	Fixing	1	No's		
	Total				
F	FLOOR CONDUITS FOR LAN/TELEPHONE CABLING WORKS(Including all Related Works)				
	Supply, installation of Al Floor raceway 2.0mm(3 equal partition as per following sizes) having 40mm depth with junction Box as for following sizes in flooring including chipping, chiseling of floor and making zarry andall related civil works.(The Floor trunking sample shall be approved by client/architect/consultant before installation)				
F1	300x300x50 mm, Floor JB with MS Sheet of 14 gauge Powder Coated with chamfered corners				
	Supply.	10	No's		
	Fixing	10	No's		
F2	150x150x50 mm, Floor JB with MS Sheet of 14 gauge Powder Coated with chamfered corners				
	Supply	15	No's		

	Fixing	15	No's		
	Total				
	G LIGHT FITTINGS				
G1	Supply,Installation, testing & commissioning of wipro make WVF 41236 2X 36W FTL(T8) with lamp WARM LIGHT				
	Supply	1	No's		
	Fixing	1	No's		
	Total				
	H UPS WIRING				
H1	Supply and wiring of Circuits for UPS power from UPS DBto Individual Tables with Suitable 2mm thick PVC Conduit and 2x2.5 Sqmm +2.5Sqmm earth wire Copper multi strand flexible pvc insulated wires with all required materials etc.				
	Supply	50	Pts.		
	Fixing	50	Pts.		
H2	Supply and wiring of Circuits for Raw power from RAW Power DB to Individual tables with Suitable 2mm thick PVC Conduit and 2x2.5Sqmm +1.5 Sqmm earth wire Copper multi strand flexible pvc insulated wires with all required materials etc.				
	Supply	100	Pts.		
	Fixing	100	Pts.		
H3	Supply and wiring of Circuits for Raw power from RAW Power DB to Individual tables with Suitable 2mm thick PVC Conduit and 2x4.0Sqmm +2.5 Sqmm earth wire Copper multi strand flexible pvc insulated wires with all required materials etc.				
	Supply	100	Pts.		
	Wiring	100	Pts.		
H4	Supply and wiring of Circuits for Sign Board power from RAW Power DB with Suitable 2mm thick PVC Conduit and 2x4.0Sqmm +2.5 Sqmm earth wire Copper multi strand flexible pvc insulated wires with all required materials etc.				
	Supply	80	Mts.		
	Wiring	80	Mts.		
	Total				
	I EARTHING				
I1	Supply, fixing, testing& commissioning of earthing Earth pit with copper plate 600x600x3mm thick, 25x6mm Copper flat, 40mm GI pipe, 100KG charcoal, 100KG salt, funnel, mesh, cover etc. digging depth up to 7'(UPS - out put dedicated)	1	No's		

I2	Supply, fixing, testing& commissioning of earthing Earth pit with GI plate 600x600x3mm thick, 25x6mm Gi_ flat, 40mm GI pipe, charcoal, salt,	1	No's		
J	Supply and fixing of earthing wire 6Sq.mm Single core	20	Mtrs		
J1	Supply and fixing of 8SWG bare Copper wire with suitable PVC conduit all required materials etc.	20	Mtrs		
J2	Supply and fixing of 8SWG bare GI wire with all materials etc.	20	Mtrs		
	Total				
K	LAN CABLING				
K1	Supply and Laying of 4Pair, UTP cat6 Lan Cable with Information outlet and Suitable 2mm Thick PVC Pipe Laying Below Flooring/Wall/Slab etc MS Junction Boxes to All Tables, Including all Related Civil Works etc All Cable Numbers to be Provided at both ends(Systemax)				
	Supply	600	M		
	Fixing	600	Pts.		
K2	Supply of 7 feet Patch Cords.(D-link)				
	Supply	20	No's		
	Fixing	20	No's		
K3	Supply of 3 feet Patch Cords.(D-link)				
	Supply	20	No's		
	Fixing	20	No's		
K4	Supply and Fixing of 24 Port Jack Panel,				
	Supply	2	No's		
	Fixing	2	No's		
K5	Supply andfixing of 22U Rack with Accesories (Self, Power Manager, Cable Manager, Fan etc)				
	Supply	1	No's		
	Fixing	1	No's		
K6	Supply and fixing of 24 Port switch				
	Supply	2	No's		
	Fixing	2	No's		
	Total				
L	TELEPHONE				
L1	Supply and fixing of RJ 11 Telephone socket with 2 Pair Telephone Cable From Each Table to EPABX, this include suitable Surface/concealed box and all required materials this Includes Supply and fixing of Suitable PVC Conduits and Cable Numbers to provided.				
	Supply	30	Sets		
	Fixing	30	Sets		
L2	Supply and Wiring of Telephone Points Wiring with 10 Pair Copper cable and suitable conduits, all required materials etc.				
	Supply	120	Mts		

	Fixing	120	Mts		
L3	Supply and fixing of 30 Pair crown box with connector and all connections etc.				
	Supply	1	No's		
	Fixing	1	No's		
	Total				
	Electrical Total				
	Grand Total (Furniture and Electrical)				

S.No.	DESCRIPTION	AMOUNT
1	INTERIOR WOOD WORK INCLUDING PARTITIONS TABLES AND FURNITURE	
2	ELECTRICAL WORK, CABLING , LAN TELEPHONE AND MISC.	
3	GST	
	GRAND TOTAL	

SEAL AND SIGNATURE OF THE TENDERER









