

**TENDER FOR THE INTERIOR WORK FOR FIRST FLOOR OF THE UNITED INDIA INSURANCE AT OUT SIDE PATIALA GATE, NABHA, PUNJAB**

| Sr. No.  | Description of item   | Quantity | Unit  | Rate | Amount |
|----------|---|----------|-------|------|--------|
| <b>1</b> | <b>FALSE CEILING</b>  |          |       |      |        |
| a.       | providing & fixing gypsum board false ceiling system using 12.5mm gypsum plaster board serewed on G.I. frame work.The frame work made on of perimetr channels 20x27x30x3657mm fixed on wall & partitions and ceiling sections 80x26x0.5x3657mm as a cross member providing 457mm c/c & the intermediate channels of 15x45x.09x3657mm as main runner at 1220 mm c/c suspended by means of G.I. angel 25x25x.05 mm from the existing ceiling by mean of M.S. rawl plug with bolts screws at 1200mm c/c max. the joints of gypsum board to be taped 3 times and sealed with jointing compound. Finished with 1 coat primer and min. 3 coats white plastic emulsion complete as per detail and specifications in drawing incl. all lights. diffuser cutting complete. | 790      | sq.ft |      |        |
| <b>2</b> | <b>TOUGHNED GLASS DOOR/GLAZING</b>  | 0        | 0     |      |        |
| a.       | PROVIDING & fixing single leaf glazed toughned door of size approximetely. 1200/900mmx2100mm fabricated with 12mm thk glass. All sides edge polished complete in all respect including transportation. Loading and fixing as per drawings and as per instruction of architect bank specification. the work should included polishing of glass. cutting wastage and fitting complete in respect.   | 80       | sq.ft |      |        |
| <b>2</b> | <b>PAINT WORK</b>   |          |       |      |        |
| a.       | P/A two or more coats of platic emulshion paint over a base course of primer including base formation with putty to a smooth & uniform finish complete in all respects.   | 3200     | sq.ft |      |        |
| b.       | P/A wood base paint & steel based paint with surface preparation with primer & chalk miti.  | 500      | sq.ft |      |        |
| <b>3</b> | <b>MISCELLENOUS</b>   | 0        | 0     |      |        |
| a.       | P/A western style w.c. urinal and wash basin with fixture.  | 1        | 0     |      |        |
| b.       | Demolation of 4 1/2" between pantary and hall.  | 66       | sq.ft |      |        |
| <b>4</b> | <b>FLOOR AND WALL TILES</b>   |          |       |      |        |
| a.       | PROVIDING AND FIXING 600X600 MM OF APPROVED SHADE PREMIUM QUALITY VITTRIFIED TILES (MAKE-NIRO GRANITE, basic price @50/- per sqft) Model no GMA 81 or 83  | 960      | sq.ft |      |        |
| b.       | 6" skirting of 600x600 mm of approved shade premium quality vittrified tiles (make Niro Granite, Basic price Rs 50/- per sqft)  | 220      | rft.  |      |        |
| c.       | providing and fixing 300x300 mm floor tiles of approved shade premium quality anti skid group v ceramic tiles ( make -Niro Granite, Basic price Rs 45/- per sqft.)  | 40       | sq.ft |      |        |
| d.       | providing and fixing 300x300 mm wall tiles of approved shade premium quality ceramic tiles ( make -Niro Granite, Basic price Rs 45/-.)  | 150      | sq.ft |      |        |
| <b>5</b> | <b>ALUMINIUM PARTITION</b>  |          |       |      |        |
| a.       | providing and fixing of powder coating a aluminium partition with 5 mm glass at electrical counter upto 4' ht.  | 90       | sq.ft |      |        |
| <b>6</b> | <b>WALL DESIGNING</b>   |          |       |      |        |





|  |  |  |  |  |  |
|--|--|--|--|--|--|
|  |  |  |  |  |  |
|  |  |  |  |  |  |
|  |  |  |  |  |  |